BRUHATH BANGALORE MAHANAGARA PALIKE,
Office of the Executive Engineer Dasarahalli Division,
Schedule-B

NAME OF WORK: Repairs reconstuction of damaged culvert in Dasarahalli in ward 15

| Sl. No | Description of work | Unit | Qty | Rate quoted by the Contractor Sri K.Nagaraj | |
|---|---|---|---|---|---|
| | | | | In Figures (Rs.) | Amount |
| 1 | 2 | 3 | 4 | 5 | 7 |
| 1 | Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter | Cum | 129.6 | 95.0 | 12312 |
| 2 | Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications | Cum | 19.44 | 4000.0 | 77760 |
| 3 | Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200 | Cum | 80.19 | 4500.0 | 360855 |
| 4 | Supplying, fitting and placing TMT bar Fe 500 reinforcement in sub-structure complete as per drawing and Technical Specifications complete as per specifications | Tonne | 8.02 | 58000.0 | 465160 |
| 5 | Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading | Cum | 129.6 | 40.0 | 5184 |

Executive Engineer

Scanned with CamScanner